No.	Items of work	Per	Rate	Quantity	Cost
			Rs. a. p.		Rs.
6	Burnt stone slabs 4″ thick, one line dressed and fixed in mortar	S.ft.	0 5 0	195	
7	Chunam plastering	Sqr.	3 0 0	56·12	
8	Cement pointing with thread lines alround basement 1 : 3	,,	3 0 0	2·00	
9	White and colour washing, two coats	,,	0 4 6	57·53	
10	Roofing with I Class Mangalore Tiles on T.W. reepers 2″×1″ including wood oiling	,,	25 0 0	19·64	
11	Ridge tiles set in mortar and cement pointing	R.ft.	0 8 0	86	
12	Ventilating tiles fixing, etc., complete	No.	2 8 0	20	
13	Teakwood wrought and put up with two coats of wood oiling	C.ft.	4 8 0	82·64	
14	Teakwood doors battened with 1″ thick including all iron fixtures complete (3″×4″)	S.ft.	1 2 0	195	
15	Teakwood windows with $\frac{5}{8}$″ diameter iron bars with iron fixtures, etc., complete	,,	1 6 0	90	
16	T.W. shelves with frame and shutters, etc., complete	,,	1 0 0	75	
17	Green painting, two coats (Mysore Government paint)	Sqr.	4 8 0	8·40	
18	Constructing sinks	Each	5 0 0	5	
19	Providing stone mortar and pestle fixed complete	,,	5 0 0	5	
20	Flooring with 3″ lime concrete 1$\frac{1}{2}$″ cement concrete and top cement plastered	Sqr.	20 0 0	10·00	
21	Levelling ground	L.S.	..	..	
22	Electric lighting	,,	..	..	
23	Providing and fixing teakwood planks with teakwood pegs, etc., complete	S.ft.	0 8 0	60	
24	Projecting the eaves by 1$\frac{1}{2}$′ extra to make up 3 from the wall at the rear side of the building.	L.S.	..	..	
25	Sinking a draw well	,,	..	..	
	Total				

B. S. NARASINGA RAO,
Executive Engineer.

SHIMOGA DIVISION.

Abstract Notification.

The attention of the public is drawn to the notification calling for tenders for extension of McGann Hospital at Shimoga published in pages 768-770 Part VI in the *Mysore Gazette*, dated 11th April 1940.

Tenders will be received by the Executive Engineer, Shimoga Division up to 3 P.M. on 27th of April 1940.

Earnest money required for the work is Rs. 1,720 which should be credited to the Treasury to "17 (*a*) P. W. Deposits" and challan enclosed.

Abstract Notification dated the 9th April 1940.

The attention of the public is drawn to the notification calling for tenders for restoring Horabyle Minor tank, near Konandur Agrahar Hobli, Tirthahalli Taluk, published in pages 854-856, Part VI in the *Mysore Gazette*, dated 18th April 1940.

Tenders will be received by the Executive Engineer, Shimoga Division up to 3 P.M. on 4th of May 1940.

Earnest money required for the work is Rs. 100 which should be credited to the Treasury to "17 (*a*) P. W. Deposits" and challan enclosed.

Notification dated 12th April 1940.

The following amounts appearing in the Public Works Deposits Register of this Division, since the past three years remain yet unclaimed. The same will be credited to Revenue if no claimant comes forward with an adequate evidence within one month from the date of this notification.

Statement of lapsed deposits for the year 1938-39.

Date of Receipt	Deposit No.	Particulars	Amount	Remarks
			Rs. a. p.	
7/1933	358	*Pujari Dasaboyee.*—Cancelled P.O. 20/1282 for P.B. 1979, dated 29th June 1933, for restoring Kaseholu Balasokere taken to deposits as the party is dead	20 0 0	
3/1934	452	*Udagalaboyee.*—Amount of P.O. 58/390, dated 30th January 1934 for A.R. of Shiralkoppa-Hirekarur Road ..	26 4 0	
9/1934	30	*Dasaboyee.*—Bill No. 6, dated 6/1934 for A.R. of Shimoga-Harihar Road	5 5 0	
10/1934	38	*Murugesam.*—Amount of F.B., dated 15th June 1934, for S.R. of T.B. at Shikarpur taken to deposits as the whereabouts of the party are not known	11 11 0	
12/1934	49	*P. Ramaboyee.*—Amount of B. I., dated 23rd September 1934 for A.R. of Shimoga-Mangalore Road taken to deposits for	1 7 0	
Do	50	*Mohadeen Sab.*—Amount recovered in the bill for rectification of bad work taken to deposits pending orders of Superintending Engineer	403 0 0	
2/1935	90	*Meerasab.*—Amount of B.I., dated 11th September 1934 for Siddan Channel Works taken to deposits as the whereabouts of the party are not known	9 12 0	
Do	93	*Davangere Hanumaboyee.*—Amount of B. I., dated 19th August 1934 for Siddan Channel Works taken to deposits for	1 13 0	
4/1935	131	*Hanumaboyee (Yenekoppa).*—Amount of underpayment in P.B. 1344, dated 5/33 for repairing the sluice of Anavatty Hirekere taken to deposits to close the work	10 0 0	
5/1935	155	*The Mysore Iron Works, Bhadravati.*—Amount of underpayment in P.B. 1377, dated 27th February 1935, for providing lightning conductor to Government House at Shimoga	6 4 0	
6/1935	170	*K. S. Shama Rao.*—Amount adjusted in B. 2, dated 29th January 1935, for A.R. of Channagiri-Malebennur Road being towards dues to Kundur Co-operative Society	2 9 10	
Do	171	*D. Hanumaboyee.*—Recovery in P.B. 1749, for strengthening to two arched bridges in 3/44 of Chitaldrug-Bhadravati Road being the value of $\frac{1}{3}$ work done to the tunnel at 2/44 of the same road as per Superintending Engineer's No. 2987, dated 24th September 1930	25 0 0	
Do	177	*T. R. Subba Rao.*—Amount of bill for A.R. of Government Middle School at Agumbe taken to deposits as the bill amount is less than Rs. 10	9 15 0	
Do	178	*Dogenahally Yeeraboyee.*—Amount of B. I, dated 9th January 1935 for A.R. of Sulekere Tank and Channels taken to deposits for closing the work	6 0 0	
Do	179	*Mahalinga.*—Amount of B. I, dated 4th September 1939, for A.R. of L.F. Dispensary at Tirthahally	8 3 0	
9/1935	33	*Ismail Berry.*—Arrears outstanding in P.B. 1860, dated 30th June 1935 for restoring Hommakki Totadamelinakere	2 0 0	

Date of Receipt	Deposit No.	Particulars	Amount	Remarks
			Rs. a. p.	
10/1935	44	*Mohadeen Sab.*—Amount of B. 1, dated 21st February 1935 for making good the damages of Siddan Channel.	2 0 0	
Do	45	*Abala Boyee.*—Amount of B. 1, dated 5th January 1935 for making good the damages of Siddan Channel ..	2 9 0	
11/1935	61	*Durgada Abdul Rahim.*—Amount taken to deposits being the repayment of advance	2 0 0	
12/1935	87	*Chillur Dasaboyee.*—Amount of B. 1, dated 10th August 1935 for A. R. of Shimoga-Harihar Road	9 3 0	
1/1936	95	Amount received from Mr. G. S. Raman, S. O. for putting cross bund across Salur Ane and Channels for storing water for sugarcane	10 0 0	
3/1936	111	*Hosangadi Baba Berry.*—Amount of B. 4, dated 15th February 1936 towards the value of stock articles issued in November 1933 and outstanding in the account now taken to deposits	34 2 0	
5/1936	140	*M. Krishnaswamy Iyengar.*—Amount of B. 1, dated 29th February 1936 for constructing Semi-Irish-Bridge taken to deposits as the party is reported dead ..	4 7 0	
Do	141	*M. Krishnaswamy Iyengar.*—Amount of B. 2, dated 14th March 1936 for constructing Semi-Irish-Bridge taken to deposits as the party is reported dead	22 2 0	
5/1936	142	*M. Krishnaswamy Iyengar.*—Amount of B. 2, dated 15th January 1936 for A. R. of Sulekere tank and channels taken to deposits as the party is reported to be dead ..	5 4 0	
Do	148	*Ismail Berry.*—Amount of B. 1, dated 3rd June 1936 for A. R. of Shimoga-Mangalore Road taken to deposits as the whereabouts of the party are not known ..	9 0 0	
6/1936	169 (2)	*T. R. Subba Rao.*—B. 1, dated 21st April 1936 for A. R. of L.F. Dispensary at Agumbe	8 0 0	
Do	169 (3)	*Bhatkal Hanumantha.*—Amount of B. 6, dated 19th June 1936 for improving and metalling ghat portion of Avinahally-Karur Road as the amount is less than Rs. 10	9 5 0	
Do	169 (4)	*Jelly Thimmiah.*—B. 5, dated 19th June 1936 for do	8 7 0	
Do	169 (9)	*Mudura.*—Amount of Rs. 3, dated 19th June 1936 for do do	6 4 0	
		Total ..	681 14 10	

Notification dated 20th April 1939.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 3 P.M. on 13th May 1940, for Improving Bhadravati Hole-honnur Road from 7 to 4—11 miles. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of February 1941.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga Division, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer on payment of annas four for each form. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a treasury challan for Rs. 600 credited to 17(a) P. W. Deposits, in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Improving Bhadravati-Hole-honnur Road from 7 to 4—11 miles in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words, as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. Chamundy brand cement should be used for the work.

14. A reserve of 5 per cent on the value of work done will be withheld from the bills towards security deposits.

Abstract estimate for improving Bhadravati-Holehonnur Road 7—4/11 Miles.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
1	Jungle clearing including cutting and removing trees	Fur.	5 0 0	14	
2	Rooting out tufty grass	Sqr.	0 3 0	2,072	
3	Picking and forming including scraping grass and removal of small mounds	Sqr.	0 1 0	3,564	
4	Earthwork excavation in mixed soils for cutting sides and forming	C.yd.	0 3 0	417	
5	Earthwork excavation of side drains	,,	0 2 6	2,567	
6	Earthwork excavation of check drain in mixed soils and using the earth for forming road	,,	0 3 0	7,920	
7	Earthwork excavation and filling in for scours and deep ruts with consolidation	,,	0 2 6	2,362	
8	Earthwork banking with watering and consolidation	,,	0 4 0	15,628	
9	Removing hard rock by blasting	,,	2 12 0	34	
10	Constructing pipe tunnels	Details will be furnished later on			
11	Constructing masonry tunnels				
12	(*a*) Constructing masonry culverts				
	(*b*) Constructing culverts at 1/6				
13	Improving the existing culvert at 6/10				
14	Acquisition of lands				
15	Rough stone boulder-filling	C.yd.	1 8 0	1,100	
16	Collecting and stacking gravel with ½ mile lead	,,	0 8 0	3,422	
17	Spreading and forming and consolidation of gravel	,,	0 4 0	3,422	
18	Supplying and fixing mile stones including figuring and painting	Each	10 0 0	4	
19	Do Furlong stones	,,	3 0 0	32	
20	Do Boundary stones	,,	1 0 0	144	
21	Do sign post R.C.C.	Each	50 0 0	1	
22	Supplying stone road roller 3′ diameter with iron fixtures, etc., complete	,,	100 0 0	1	
23	Forming approaches to Kage Kodamaggihalla and Hulibasappan halla	,,	250 0 0	1	

Notification dated 20th April 1940

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 3 P.M. on 13th May 1940, for Improving Bhadravati-Hole-honnur Road from 4 to 6 miles. An approximate estimate of quantities is given below.

These quantities are not guaranteed. The work should be completed by the end of February 1941.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga Division between the hours of 11 A.M. and 5 P.M.

3. Tender should be submitted on printed forms which may be obtained from the Executive Engineer on payment of annas four for each form. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a Treasury chellan for Rs. 360, credited to "17(a) P.W. Deposits in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Improving Bhadravathi Holehonnur Road from 4 to 6 miles," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Eecutive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. Chamundy brand cement should be used for the work.

14. A reserve of 5 per cent on the value of work done will be withheld from the bills towards security deposits.

Abstract estimate for improving Bhadravati-Holehonnur Road 4 to 6 miles.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
1	Jungle clearing including cutting and removing trees	Fur.	5 0 0	22	
2	Rooting out Tufty grass	Sqr.	0 3 0	1,624	
3	Picking and forming including scraping grass and removal of small mounds	,,	0 1 0	2,376	
4	Earthwork excavation in mixed soils for cutting sides and forming	C.yd.	0 3 0	1,407	
5	Earthwork excavation of side drains	,,	0 2 6	1,540	
6	Earthwork excavation of check drains in mixed soils and using earth for forming road	,,	0 3 0	4,540	
7	Earthwork excavation and filling in for scours and deep ruts with consolidation	C.yd.	0 2 6	..	
8	Earthwork banking with watering and consolidation	,,	0 4 0	10,881	
9	Removing hard rock by blasting	,,	2 12 0	38	
10	Constructing pipe tunnels				
11	Constructing masonry tunnels				
12	(*a*) Constructing masonry culverts				
	(*b*) Constructing culvert at $\frac{1}{6}$		Details will be furnished later on		
13	Improving the existing culvert at 6/10				
14	Acquisition of lands				
15	Rough stone boulder filling	C.yd.	1 8 0	..	
16	Collecting and stacking gravel with $\frac{1}{2}$ mile lead	,,	0 8 0	2,347	

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
17	Spreading, forming and consolidating gravel	Cyd.	0 4 0	2,347	
18	Supplying and fixing mile stone including figuring and painting	Each	10 0 0	3	
19	Do furlong stones	,,	3 0 0	21	
20	Do houndary stones	,,	1 0 0	96	
21	Do sign post R.C.C.	,,	50 0 0	..	
22	Supplying stone road rollers 3' diameter with iron fixtures, etc., complete	,,	100 0 0	1	
23	Forming approaches to Kage Kodamaggi Halla and Huli Basappanhalla	,,	250 0 0	1	

D. A. HUKERI,
Executive Engineer.

KADUR DIVISION.

Abstract Notification dated 4th April 1940.

The attention of the public is invited to the Notification published on pages 831-834 of Part VI of the *Mysore Gazette* dated 11th April 1940 calling for tenders for the work of constructing "a new pair of masonry settling tanks for Chikmagalur Town Water-supply" at Chikmagalur. The last date of the receipt of tender in this office is 25th April 1940.

C. NARAYANASWAMI SETTI,
For *Executive Engineer.*

ANJANAPUR DIVISION.

Abstract Notification.

The attention of the public is hereby invited to the detailed notification calling for tenders for restoring Muthagi Jagalikatte, Major Tank, Regd. No. 834, Shikarpur Taluk, published in pages 856-859, Part VI of the *Mysore Gazette*, dated 18th April 1940.

Last date of receipt of the tender is 3 P.M. on the 10th May 1940. Each tender should accompany with a duplicate challan for having credited the deposit amount of Rs. 680 into the Treasury under "17 (*a*) P. W. Deposits."

M. V. KRISHNASWAMY IYENGAR,
Executive Engineer.

MISCELLANEOUS DEPARTMENTS.

OFFICE OF THE INSPECTOR-GENERAL OF POLICE IN MYSORE, BANGALORE.

Notice No. T. C. 295—37-38, *dated 19th November* 1937.

The public are hereby informed that an Avery's Weigh-bridge to weigh motor vehicles is erected in the Office of the Inspector-General of Police in Mysore, Cenotaph Road, Bangalore City, and that motor vehicles brought for weighment will be weighed on payment of a fee of Rs. 10 for each weighment. A certificate of weighment will invariably be issued with each weighment so made.

F. A. HAMILTON,
Inspector-General of Police.

OFFICE OF THE SUPERINTENDENT, GOVERNMENT PRINTING, IN MYSORE, BANGALORE.

Abstract Notification dated 10th April 1940.

The attention of the public is invited to the detailed notification dated 10th April 1940, published on pages 835-836 of Part VI of the *Mysore Gazette*, dated 11th April 1940, regarding the sale of unserviceable articles at the Government Central Press, Bangalore, on Monday the 29th April 1940.

B. KRISHNASWAMY CHETTY,
Superintendent.